

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24703-00-00
Spot: SENE Sec/Twnshp/Rge: 2-19S-15W
990 feet from N Section Line, 330 feet from E Section Line
Lease Name: COBB Well #: 1
County: BARTON Total Vertical Depth: 3644 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3643 | | 150 SX |
| SURF | 8.625 | 936 | | 400 SX |

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 05/20/2014 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 600 # hulls and 14 sx gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/20/2014 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1500' and 970'. Ran tubing to 3300' and pumped 14 sx gel followed by 70 sx cement /100 # hulls. Pulled tubing to 1500' and pumped 60 sx cement w/100 # hulls. Pulled tubing to 975' and pumped 50 sx cement w/100 # hulls. Pulled tubing to 500'. Circulated cement to surface on casing with 50 sx cement. Circulated cement on surface pipe with 170 sx cement. Pulled tubing and topped off with 15 sx cement.

GPS: 38.43166 -098.94169

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3600 | 3602 | | |
| 3587 | 3589 | | |

Remarks: COPELAND ACID AND CEMENTING

Plugged through: ^{T&G}CSG

KCC WICHITA

MAY 28 2014

RECEIVED

District: 04

Signed Bruce Rodie
6/09/14 (TECHNICIAN)

CM

MAY 22 2014

Form CP-2/3