

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25752-00-00
Spot: NESESWSE Sec/Twnshp/Rge: 15-19S-22W
440 feet from S Section Line, 1510 feet from E Section Line
Lease Name: KLEWENO Well #: 2-15
County: NESS Total Vertical Depth: 4337 feet

Operator License No.: 33922
Op Name: MUSTANG ENERGY CORPORATION
Address: PO BOX 1121
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	215		WITH 150 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/02/2014 3:00 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: 1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 780' WITH 80 SX CMT. 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: DANIEL SELLERS Witness Type: NONE
Date/Time Plugging Completed: 04/02/2014 5:00 PM KCC Agent: DANIEL SELLERS

Actual Plugging Report:

Perfs:

1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 780' WITH 80 SX CMT. 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY QUALITY.

Plugged through: DP

KCC WICHITA
APR 28 2014
RECEIVED

District: 01

RECEIVED
APR 22 2014

Signed Daniel Sellers
6/27/14 (TECHNICIAN)

KCC DODGE CITY