

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-20606-00-00  
Spot: SWNENWSE Sec/Twnshp/Rge: 10-17S-24W  
2022 feet from S Section Line, 1870 feet from E Section Line  
Lease Name: AMSTUTZ - AB Well #: 2  
County: NESS Total Vertical Depth: 4479 feet

Operator License No.: 3553  
Op Name: CITATION OIL & GAS CORP.  
Address: 14077 CUTTEN RD PO BOX 690688  
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1155		
CIBP		1790		
CIBP		4250		
CIBP		4463		
CIBP		4479		
PROD	5.5	4464	0	WITH 75 SX CMT
SURF	8.625	220		WITH 75 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/21/2014 11:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: NEIL PFANNENSTIEL Company: CITATION OIL & GAS Phone: (281) 891-1000

Proposed Plugging Method: TBG IS STUCK IN HOLE, WORK TO GET FREE. PLUG ON BOTTOM WITH 50 SX CMT & 150# HULLS. PULL TBG TO 1800' & CIRCULATE TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/21/2014 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

**\*\*WELL WAS SQUEEZED AT 1135' WITH 260 SX CMT\*\* WORKED 3 DAYS TO FREE TBG. COULD ONLY GET 2600' OF TBG. RUN TBG TO 2595' & SPOT 50 SX CMT & 150# HULLS. PULL TBG TO 1803' & PUMPED 155 SX CMT & 300# HULLS. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 25 SX CMT. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 500#. LEFT TUBING IN HOLE FROM 2600' TO 4464'.**

Perfs:

Top	Bot	Thru	Comments
4464	4479		

Received  
KANSAS CORPORATION COMMISSION  
**JUN 06 2014**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

MAY 30 2014

KCC DODGE CITY

Signed

*Michael Maier*  
✓ 6/10/14

(TECHNICIAN)

51