

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25093-00-00
Spot: SWNESE Sec/Twnshp/Rge: 15-20S-13W
2150 feet from S Section Line, 420 feet from E Section Line
Lease Name: B.W. Well #: 2
County: BARTON Total Vertical Depth: 3600 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3596	2293	165 SX
SURF	8.625	329		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/23/2014 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/23/2014 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped off with 5 sx cement. Cut casing at 2293'. Pulled casing to 1550' and pumped 125 sx cement w/100 # hulls. Pulled casing to 950' and pumped 50 sx cement w/100 # hulls. Pulled casing to 700' and pumped 50 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface with 100 sx cement. Pulled casing. Hole stayed full.

GPS: 38.31033 -098.73860

Perfs:

Top	Bot	Thru	Comments
3498	3502		
3394	3400		
3378	3382		
3358	3362		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

KCC WICHITA

MAY 21 2014

RECEIVED

District: 04

Signed

Bruce Rodie
6/09/14 (TECHNICIAN)

CM

APR 25 2014