

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-141-20063-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 3-10S-15W  
330 feet from S Section Line, 330 feet from W Section Line  
Lease Name: HOBROCK Well #: 1  
County: OSBORNE Total Vertical Depth: 3620 feet

Operator License No.: 32278  
Op Name: TENGASCO, INC.  
Address: 1327 NOOSE RD PO BOX 458  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3618		175 SX
SURF	8.625	244		140 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/23/2014 9:30 AM  
Plug Co. License No.: 32332 Plug Co. Name: FISCHER WELL SERVICE, INC.  
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/23/2014 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Drilled CIB plug out at 3175'. Perforated at 1240'. Ran tubing to 3510' and pumped 125 sx cement w/300 # hulls. Pulled tubing to 1740' and pumped 150 sx cement w/200 # hulls. Cement circulated. POOH. Hooked to braden head and pumped 35 sx cement at 250 psi. Topped off casing w/15 sx cement.

GPS: 39.20634 -098.99077

Perfs:

Top	Bot	Thru	Comments
3243	3512		
3218	3232		

KCC WICHITA  
JUN 05 2014  
RECEIVED

Remarks: QUALITY CEMENTING TICKET # 3137

Plugged through: TBG

District: 04

Signed Ray Dinkel  
(TECHNICIAN)

✓ 6/11/14

CM

MAY 27 2014