

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-19410-00-00  
Spot: SWNESE Sec/Twnshp/Rge: 23-10S-20W  
1650 feet from S Section Line, 990 feet from E Section Line  
Lease Name: PAGE Well #: 3  
County: ROOKS Total Vertical Depth: 3800 feet

Operator License No.: 6484  
Op Name: ANDERSON ENERGY, INC.  
Address: 300 W DOUGLAS AVE, STE 410  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3799		550 sx
SURF	8.625	255		155 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/07/2014 2:00 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: PRESTON DREILING Company: DREILING EXPLORATION, LLC. Phone: (785) 639-2099

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
CIBP: 3545'  
Perforations: 3460' - 3484'

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/07/2014 4:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 2200', 1613' and 950'. Ran tubing to 3110' and pumped 150 sx cement w/300 # hulls. Pulled tubing to 1700' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 800' and pumped 125 sx cement to circulate cement to surface. Pulled all tubing and topped off 5 1/2" casing w/25 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 30 sx cement. Shut in pressure 50 psi.

GPS: 39.16612N -099.51586W

Perfs:

Top	Bot	Thru	Comments
3476	3484		
3460	3466		

Remarks: GLOBAL TICKET # 1319

Plugged through: TBG

KCC WICHITA  
MAY 21 2014  
RECEIVED

District: 04

Signed Pat Bedore  
6/05/14 (TECHNICIAN)

CM

MAY 16 2014