

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-20211-00-00  
Spot: S2NENESE Sec/Twnshp/Rge: 27-29S-13W  
2132 feet from S Section Line, 313 feet from E Section Line  
Lease Name: HARREL D Well #: 6  
County: PRATT Total Vertical Depth: 4616 feet

Operator License No.: 34320  
Op Name: LIASSO ENERGY LLC  
Address: PO BOX 465  
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4611	2200	WITH 250 SX CMT
SURF	8.625	1033		WITH 350 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/07/2014 11:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: SAND BACK TO 4560' & PUT 5 SX CMT ON TOP OF SAND BRIDGE. PLUG AT 1060' WITH 15 SX GEL & 50 SX CMT. PLUG AT 730' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/08/2014 5:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4546' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 1060' WITH 15 SX GEL & 50 SX CMT WITH NO RETURNS. 2ND PLUG AT 730' WITH 40 SX CMT. HOLE NEVER DID CIRCULATE. LAID DOWN REST OF CASING. SHUT DOWN. LET CMT SET. 5/8/14: RUN IN & TAG. TOC @ 800'. FLUID LEVEL AT 150'. RUN TBG IN TO 300'. COULD NOT ESTABLISH CIRCULATION. SPOT 25 SX COMMON CMT WITH 3% CC. NO RETURNS. PULL TBG UP HOLE & LET CMT SET. TAG TOC @ 800'. WAIT ON DRILLING MUD. LOAD HOLE WITH MUD. CIRCULATED CMT FROM 300' TO SURFACE. LAY TBG DOWN. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4611	4616		

KCC WICHITA  
MAY 20 2014  
RECEIVED

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer  
6/09/14 (TECHNICIAN)

RECEIVED  
MAY 16 2014  
KCC DODGE CITY

Form CP-23