

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24243-00-01
Spot: SENESESW Sec/Twnshp/Rge: 7-18S-23W
672 feet from S Section Line, 2513 feet from W Section Line
Lease Name: HERRICK OWWO Well #: 1-7
County: NESS Total Vertical Depth: 4500 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: 1700 N WATERFRONT PKWY BLDG 12
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4242		
CIBP		4320		
PC		1650		CEMENTED WITH 200 SX CMT. 20 SX CMT CIRCULATED TO PIT.
PROD	5.5	4484		CEMENTED WITH 170 SX CMT
SURF	8.625	232		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/08/2014 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: KYLE RANDA Company: MULL DRILLING Phone: (785) 798-3306

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 05/08/2014 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 75 SX CMT WITH 250# HULLS & DISPLACED TO 3850'. WATER TO 1630'.
PUMP 235 SX CMT FROM 1630' TO 0'. PRESSURED 8 5/8" X 5 1/2" ANNULUS TO 300
PSIG WITH 235 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4360	4368		
4348	4368		
4278	4281		
4150	4154		
4130	4136		
4127	4130		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

KCC WICHITA

MAY 20 2014

RECEIVED

District: 01

RECEIVED

MAY 12 2014

KCC DODGE CITY

Signed

Michael Maier
6/10/14
(TECHNICIAN)

SP