

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-21856-00-00  
Spot: N2NESE Sec/Twnshp/Rge: 31-15S-21W  
2310 feet from S Section Line, 660 feet from E Section Line  
Lease Name: HALBLEIB A Well #: 1  
County: TREGO Total Vertical Depth: 4420 feet

Operator License No.: 5086  
Op Name: PINTAIL PETROLEUM, LTD.  
Address: 225 N MARKET STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4419		625 SX
SURF	8.625	258		160 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/06/2014 1:00 PM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: \_\_\_\_\_ Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: Perforated at 4262' - 4317'.  
Ordered 400 sx 60/40 pozmix 4% gel cement, 400 # hulls and 10 sx gel.  
DV Tool 1738' w/450 sx cement

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/06/2014 4:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4096' and pumped 10 sx gel followed by 75 sx cement and 200 # hulls. Pulled tubing to 1825' and pumped 125 sx cement. Good circulation of cement. Pulled tubing out of hole and topped off with 15 sx cement. Tied on to back side and squeezed with 10 sx cement. Shut in pressure 100 psi. Hole standing full.

GPS: 38.70294 -099.69331

Perfs:

Top	Bot	Thru	Comments
4262	4317		

**KCC WICHITA**

Remarks: SWIFT CEMENT TICKET # 26204

MAY 20 2014

Plugged through: TBG

RECEIVED

District: 04

Signed [Signature]  
6/09/14 (TECHNICIAN)

CM

MAY 13 2014