

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21913-00-00
Spot: W2NESESE Sec/Twnshp/Rge: 31-15S-21W
990 feet from S Section Line, 380 feet from E Section Line
Lease Name: HALBLEIB-A Well #: 2
County: TREGO Total Vertical Depth: 4390 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4387		300 SX
SURF	8.625	255		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/08/2014 9:30 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: _____ Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Perforations at 4260' - 4306'
Port Collar at 1768' w/414 sx cement.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/08/2014 12:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3968' and pumped 10 sx gel followed by 75 sx cement w/200 # hulls. Pulled tubing to 1950' and pumped 140 sx cement. Good circulation of cement. Pulled tubing out and topped off with 20 sx cement. Tied on to back side and squeezed with 5 sx cement. Shut in pressure 350 psi. Hole standing full.

GPS: 38.69932 -099.69243

Perfs:

Top	Bot	Thru	Comments
4260	4306		

KCC WICHITA

Remarks:

Plugged through: TBG

MAY 20 2014

RECEIVED

District: 04

Signed


(TECHNICIAN)

CM

MAY 13 2014