

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-045-20079-00-00  
Spot: SWNWSENE Sec/Twnshp/Rge: 11-15S-20E  
3440 feet from S Section Line, 1102 feet from E Section Line  
Lease Name: WEARLY Well #: 115 F  
County: DOUGLAS Total Vertical Depth: 918 feet

Operator License No.: 34350  
Op Name: ALTAVISTA ENERGY, INC.  
Address: 4595 K-33 HIGHWAY PO BOX 128  
WELLSVILLE, KS 66092

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.375	916		110 SX
SURF	6.25	96		25 SX

Well Type: EOR UIC Docket No: E08295.45 Date/Time to Plug: 04/08/2014 11:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: BRYAN MILLER Company: ALTAVISTA ENERGY, INC. Phone: (785) 883-4057

Proposed Plugging Method: WASH THROUGH 1", FILL WITH CEMENT THROUGH 1" FROM BOTTOM TO TOP.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE  
Date/Time Plugging Completed: 04/08/2014 12:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

WASHED 1" PIPE DOWN TO TD AND PUMPED 12 SACKS OF CEMENT. PULLED THE PIPE UP TO 450' AND PUMPED 10 SACKS OF CEMENT TO THE SURFACE. PULLED THE PIPE OUT AND TOPPED OFF WITH AN ADDITIONAL 3 SACKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
854	895		

RECEIVED  
MAY 29 2014  
KCC Chanute Dist. #3  
TH

Remarks:  
Plugged through: TBG

District: 03

Signed Taylor Herman  
(TECHNICIAN)

cc to UIC 6/03/14  
6/05/14

KCC WICHITA  
JUN 02 2014  
RECEIVED