

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00029-00-01
Spot: SWSW Sec/Twnshp/Rge: 5-3S-16W
660 feet from S Section Line, 4620 feet from E Section Line
Lease Name: BREIT/BOLAN Well #: 1-5
County: PHILLIPS Total Vertical Depth: 1000 feet

Operator License No.: 33599
Op Name: BARLINE OIL, LLC
Address: 7804 E FUNSTON, STE. 209
WICHITA, KS 67207

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 273 | | |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/03/2014 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TOM BEREN Company: ALLIED CEMENT COMPANY Phone: (785) 639-5727

Proposed Plugging Method:
Ordered 300 sx 60/40 pozmix 4% gel cement w/300 # hulls.
Ordered an additional 150 sx 60/40 pozmix 4% gel cement.
8 5/8" surface pipe previously set at 273'.
Operator was washing well down and got outside of hole at 1000'.

Plugging Proposal Received By: CHRIS NEELEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/03/2014 2:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Ran tubing to 980' and pumped 300 sx cement w/100 # hulls. Had circulation after about 15 bbl of slurry. Ran out of cement before getting it to surface. Allied called for more cement. Pulled all tubing out of hole while waiting for more cement to arrive. Ran tubing back in hole and tagged at 260'. Pulled tubing up to 255' and pumped 75 sx cement to circulate cement to surface. Pulled all tubing and topped off 8 5/8" surface pipe w/15 sx cement.

GPS: 39.81620N -099.15790W

Remarks: ALLIED TICKET # 55356

Plugged through: TBG

KCC WICHITA
JUN 12 2014
RECEIVED

District: 04

Signed Pat Bedore
(TECHNICIAN)

CM

JUN 04 2014