

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23757-00-00
Spot: N2SENE5W Sec/Twnshp/Rge: 30-9S-21W
1765 feet from S Section Line, 2310 feet from W Section Line
Lease Name: SMITH Well #: 1
County: GRAHAM Total Vertical Depth: 3987 feet

Operator License No.: 34392
Op Name: TEXKAN EXPLORATION LLC
Address: 307 NW 3RD ST PO BOX H
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3987	0	100 SX
SURF	8.625	227		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/09/2014 1:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TOM BERENS Company: EXPRESS WELL SERVICE & SUPPL Phone: (785) 688-4040

Proposed Plugging Method: DV Tool at 1869' w/550 sx cement. CIBP at 3890'. Perforations at 3763' - 3766', 3742' - 3744' and 3728' - 3730'.
Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls and 11 sx gel.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/09/2014 3:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3860' and pumped 11 sx gel followed by 75 sx cement and 200 # hulls. Pulled tubing to 1948' and pumped 100 sx cement. Pulled tubing to 1003' and pumped 100 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 36 sx cement. Tied on to backside and squeezed with 40 sx cement. Shut in pressure 200 psi.

Perfs:

Top	Bot	Thru	Comments
3903	3906		
3575	3578		
3574	3766		

Remarks: ALLIED CEMENT TICKET # 062068

Plugged through: TBG

KCC WICHITA

MAY 20 2014

RECEIVED

District: 04

Signed

Marvin Mills
(TECHNICIAN)
✓ 6/11/14

CM

Form CP-2/3

MAY 13 2014