

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-01804-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 34-21S-13W
329 feet from S Section Line, 339 feet from W Section Line
Lease Name: GATES A Well #: 1
County: STAFFORD Total Vertical Depth: 3732 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3725	0	WITH 125 SX CMT
SURF	8.625	291		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/27/2014 10:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: CHRIS SCHOENHOFER Company: CHARTER ENERGY Phone: (620) 793-9090

Proposed
Plugging
Method:

SAND BOTTOM WITH 5 SX CMT. PULL TBG TO 750' & PERFORATE & CIRCULATE CMT.

Plugging Proposal Received By: NATHAN WILLIS WitnessType: PARTIAL
Date/Time Plugging Completed: 05/27/2014 11:45 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

5/23/14: SANDED BOTTOM TO 3000' WITH 5 SX CMT. PULLED TBG TO 750' & PUMPED 395 SX CMT. DID NOT CIRCULATE. SHUT DOWN. 5/27/14: RUN TBG TO 590' & PUMPED 60 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE & PRESSURED TO 300#.

Perfs:

Top	Bot	Thru	Comments
3725	3732		
3350	3557		

Remarks: USED 60/40 POZMXIX 4% GEL BY QUALITY.

Plugged through: TBG

Received
KANSAS CORPORATION COMMISSION

JUN 06 2014

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed

Michael Maier
6/10/14

(TECHNICIAN)

RECEIVED

MAY 30 2014

KCC DODGE CITY

Form CP-2/3