

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-20217-00-00
Spot: NESWNESE Sec/Twnshp/Rge: 22-30S-12W
1864 feet from S Section Line, 702 feet from E Section Line
Lease Name: MEAIRS Well #: 1
County: BARBER Total Vertical Depth: 3800 feet

Operator License No.: 5047
Op Name: RUPE OIL COMPANY, INC.
Address: 111 WHITTIER # 1000 PO BOX 783010
WICHITA, KS 67207

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 2815 | | WITH 4 SX CMT |
| PROD | 5.5 | 3200 | 1960 | WITH 150 SX CMT |
| SURF | 8.625 | 286 | | WITH 250 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/14/2014 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 2815' & 2 SX CMT. PLUG AT 680' WITH 10 SX GEL & 50 SX CMT. PLUG AT 310' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: PARTIAL
Date/Time Plugging Completed: 05/15/2014 4:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 2815' & PUT 4 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 680' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 50' WITH 25 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3100 | 3104 | | |
| 2865 | 2869 | | |

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

KCC WICHITA
MAY 20 2014
RECEIVED

District: 01

Signed Stephen J. Pape
(TECHNICIAN)

RECEIVED
MAY 16 2014

KCC DODGE CITY

Form CP-2/3