

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22829-00-00
Spot: NENW Sec/Twnshp/Rge: 18-35S-35W
4177 feet from S Section Line, 3275 feet from E Section Line
Lease Name: GARMAN Well #: 2-18
County: STEVENS Total Vertical Depth: 6768 feet

Operator License No.: 5263
Op Name: MIDWESTERN EXPLORATION COMPA
Address: 3500 S BOULEVARD STE 2B
EDMOND, OK 73013

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	40		40 SX
PROD	5.5	6735	3814	175 SX
SURF	8.625	1679		300 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/04/2014 10:30 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: ON BOTTOM PUMP 25 SX CMT WITH 150# HULLS. PLUG AT 1710' WITH 10 SX GEL & 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/04/2014 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 50 SX CMT, 150# HULLS THEN 25 SX CMT. DISPLACE WITH MUD TO 6400' & PRESSURE TO 800#. HOLDING. 1ST PLUG AT 1710' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6600	6610		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

Received
KANSAS CORPORATION COMMISSION

JUN 11 2014

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed

Ken Jehlik
6/11/14 (TECHNICIAN)

RECEIVED

JUN - 9 2014

KCC DODGE CITY

Form CP-2/3