

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-21587-00-00
Spot: SWSESENW Sec/Twnshp/Rge: 20-28S-4E
2868 feet from S Section Line, 3078 feet from E Section Line
Lease Name: KEYS A Well #: 2
County: BUTLER Total Vertical Depth: 2480 feet

Operator License No.: 31389
Op Name: NOBLE PETROLEUM, INC.
Address: 3101 N ROCK RD STE 125
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2478	502	100 SX
SURF	8.625	213		80 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/17/2014 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: MIKE KISER Company: HIZEY SERVICE & SUPPLY Phone: (316) 775-5496

Proposed Plugging Method: AS PER KCC RULES & REGS / CEMENT 50' ABOVE PERF @ 2320', 250'-0' CIRC.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/17/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2437', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 40 SXS 60/40 POZMIX 4% GEL, 3% CC, 3/4# POLY FLAKE & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 2032'. RIH ON WIRELINE, CUT CASING @ 502', LAYED DOWN 14 JOINTS 5 1/2" CASING (502'). RIH W/TBG @ 265', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION. MIXED & PUMPED 115 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. CONSOLIDATED CEMENT TICKET #42935.

Perfs:

Top	Bot	Thru	Comments
2436	2444	CSG	

KCC WICHITA

Remarks: COMPLIANCE / DENIED TA

APR 28 2014

Plugged through: TBG

RECEIVED

District: 02

Signed Duane Krueger
6/09/14 (TECHNICIAN)

JK