

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-10868-00-01  
Spot: NWSWSWSE Sec/Twnshp/Rge: 12-22S-12W  
380 feet from S Section Line, 2370 feet from E Section Line  
Lease Name: WILLINGER Well #: 4  
County: STAFFORD Total Vertical Depth: 3771 feet

Operator License No.: 32432  
Op Name: LA VETA OIL & GAS, LLC  
Address: 312 N BUFFALO  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3090		WITH 2 SX CMT
L1	4.5	3686		
PROD	5.5	3615	0	WITH 215 SX CMT
SURF	8.625	205		WITH 175 SX CMT

Well Type: SWD UIC Docket No: D21258.0 Date/Time to Plug: 05/09/2014 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: CIBP @ 3090'. PERFORATE AT 600' & CIRCULATE CMT. PUMP 50 SX CMT DOWN BACKSIDE IF POSSIBLE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/09/2014 11:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CIBP @ 3090' WITH 2 SX CMT. PERFORATE AT 600' & PUMPED 60 SX CMT THROUGH TBG. PULLED TBG & TOPPED OFF WITH 10 SX CMT. TIED ONTO CASING. CASING PRESSURED TO 1000# & COULDN'T PUMP IN TO. TIED ONTO BACKSIDE & PRESSURED RIGHT UP, BLEW VALVE APART.

Perfs:

Top	Bot	Thru	Comments
3686	3771	OH	

KCC WICHITA

MAY 30 2014

RECEIVED

Remarks: \*\*COMPLIANCE ISSUE: FAILED MIT\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed Michael J. Maier (TECHNICIAN)

RECEIVED

MAY 21 2014

KCC DODGE CITY

cc to UIC 6/05/14  
16/11/14