

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02157-00-00
Spot: SWSNW Sec/Twnshp/Rge: 14-10S-20W
2970 feet from S Section Line, 1650 feet from W Section Line
Lease Name: STITHEM Well #: 20
County: ROOKS Total Vertical Depth: 3786 feet

Operator License No.: 32638
Op Name: NADEL AND GUSSMAN LLC
Address: 15 E 5TH ST STE 3200
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3784		125 SX
SURF	8.625	159		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/09/2014 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: DUANE WOOD Company: MIKE'S TESTING & SALVAGE, INC Phone: (785) 737-3051

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Tubing parted at 1400'. Tried for over a week with overshot, wash pipe, flat bottom mill, etc. with no progress

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 05/09/2014 12:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 180' and 980'. Ran tubing to 1400' and pumped 50 sx cement. Pulled tubing to 930' and circulated cement w/175 sx cement and 400 # hulls. Tied onto casing and pumped 30 sx cement to 300 psi. Tied onto backside and pumped 20 sx cement to 200 psi.

Perfs:

Top	Bot	Thru	Comments
3682	3706		
3646	3666		

Remarks: COPELAND CEMENTING

Plugged through: TBG

KCC WICHITA

JUN 12 2014

RECEIVED

District: 04

Signed _____

(TECHNICIAN)

JUN 05 2014