

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21470-00-01
Spot: W2E2E2SW Sec/Twnshp/Rge: 1-12S-25W
1363 feet from S Section Line, 3186 feet from E Section Line
Lease Name: SCHIMKOWITSCH CP Well #: 5
County: TREGO Total Vertical Depth: 4170 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4164		200 SX
SURF	8.625	248		275 SX

Well Type: EOR UIC Docket No: E23601.2 Date/Time to Plug: 05/08/2014 8:00 AM
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC
Proposal Rcvd. from: THOMAS ATKINS Company: ULTIMATE WELL SERVICE, LLC Phone: (785) 216-0155

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/500 # hulls.
DV Tool at 2168' w/400 sx cement.
Perforations: 4069' - 4074'

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/08/2014 3:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4050' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 2650' and pumped 100 sx cement w/100 # hulls. Good circulation of cement. Pulled tubing out. Topped off casig w/40 sx cement. Tied to back side and squeezed with 10 sx cement. Shut in pressure 100 psi.

Perfs:

Top	Bot	Thru	Comments
4069	4074		

KCC WICHITA

Remarks: ALLIED CEMENT TICKET # 055239

MAY 20 2014

Plugged through: TBG

RECEIVED

District: 04

Signed Marvin Mills
(TECHNICIAN)

CM

MAY 13 2014

Form CP-2/3