

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-21390-00-00  
Spot: SENVSESE Sec/Twnshp/Rge: 26-16S-25W  
762 feet from S Section Line, 761 feet from E Section Line  
Lease Name: BEAHM Well #: 1  
County: NESS Total Vertical Depth: 4530 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PKWY  
WICHITA, KS 67206

| String | Size  | Depth (ft) | Pulled (ft) | Comments        |
|--------|-------|------------|-------------|-----------------|
| CIBP   |       | 1300       |             | WITH 2 SX CMT   |
| PROD   | 5.5   | 4518       | 0           | WITH 125 SX CMT |
| SURF   | 8.625 | 318        |             | WITH 250 SX CMT |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/09/2014 10:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: JORDAN HAYES Company: OIL PRODUCERS Phone: (316) 303-4691

Proposed Plugging Method: CIBP @ 4348' WITH 2 SX CMT. PERFORATE AT 1900' WITH 15 SX GEL & 50 SX CMT. PERFORATE AT 1150' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: NATHAN WILLIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/09/2014 2:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO BOTTOM & SPOT 50 SX CMT & 200# HULLS. PULL TBG & SET CIBP @ 1300' WITH 2 SX CMT. PERFORATE AT 1150' & PUMP 175 SX CMT. DID NOT CIRCULATE. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 500#. TOPPED OFF CASING WITH 50 SX CMT.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4416 | 4418 |      |          |
| 4398 | 4404 |      |          |

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED 60/40 POZMIX 4% GEL BY ALLIED. APR 28 2014

Plugged through: TBG

RECEIVED

District: 01

Signed Michael Maier  
6/8/14 (TECHNICIAN)

RECEIVED

APR 21 2014

KCC DODGE CITY

RAY