

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15331-00-00
Spot: SESENE Sec/Twnshp/Rge: 13-17S-11W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: MYERS Well #: 2 (A-1)
County: BARTON Total Vertical Depth: 3311 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3302		100 SX
SURF	10	305		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/17/2014 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: KEVIN WILES Company: AMERICAN WARRIOR Phone: (620) 275-9231

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Junk in well at 1600'. Tried to drill and mill out for 3 days and got down to 1800'. Will plug at this depth.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/17/2014 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1300', 650' and 275'.
Ran tubing to 1750' and pumped 150 sx cement w/200 # hulls 3 % cc. Pulled tubing to 950' and pumped 60 sx cement w/100 # hulls. Pulled tubing to 650' and pumped 70 sx cement w/100 # hulls. Pulled tubing to 300'. Circulated cement to surface with 95 sx cement. Pulled tubing and topped off with 20 sx cement.
GPS: 38.57359 -098.48125

Perfs:

Top	Bot	Thru	Comments
3302	3311		

Remarks: ALLIED CEMENT CO.

Plugged through: CSG

KCC WICHITA
MAY 21 2014
RECEIVED

District: 04

Signed Bruce Rodie
(TECHNICIAN)

6/05/14

cm

APR 29 2014