

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-20772-00-00
Spot: SESENE Sec/Twnshp/Rge: 7-24S-4W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: K MEIER Well #: 3
County: RENO Total Vertical Depth: 3373 feet

Operator License No.: 8653
Op Name: PETROLEUM TECHNOLOGIES, INC.
Address: 801 W 47TH ST STE 412
KANSAS CITY, MO 64112

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3363	1790	175 SX
SURF	8.625	445		375 SX
SURF	8.625	446		325 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/07/2014 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (913) 638-6398

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 04/07/2014 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3280' CAPPED WITH 5 SXS CEMENT ON TOP. CUT CASING PIPE OFF @ 1790' PULLED CASING TO 650' SPOTTED 35 SXS CEMENT. TAGGED TOC @ 415'. CIRCULATED CEMENT TO SURFACE FROM 415' WITH 200 SXS OF CEMENT. CHECKED TOP PLUG 4/8/14 DOWN 2' OK TO CLOSE.

Perfs:

Top	Bot	Thru	Comments
3363	3373		

KCC WICHITA
APR 29 2014
RECEIVED

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, 60/40 4% POS MIX, TICKET #40054, PAST 10 YEARS WITH NO LEASE.

Plugged through: CSG

District: 02

Signed B Hope
6/07/14 (TECHNICIAN)