

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-00945-00-00  
Spot: SWNWSE Sec/Twnshp/Rge: 23-10S-20W  
1650 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: PAGE Well #: 2  
County: ROOKS Total Vertical Depth: 3786 feet

Operator License No.: 6484  
Op Name: ANDERSON ENERGY, INC.  
Address: 300 W DOUGLAS AVE, STE 410  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3785		50 SX
SURF	8.625	254		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/08/2014 8:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: PRESTON DREILING Company: DREILING EXPLORATION, LLC. Phone: (785) 639-2099

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Perforations: 3769' - 3774'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/08/2014 10:45 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 2250', 1650' and 1000'. Ran tubing to 2700' and pumped 150 sx cement w/300 # hulls. Pulled tubing to 1300' and pumped 200 sx cement w/200 # hulls to circulate cement to surface. Pulled all tubing and topped off 5 1/2" casing w/20 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 10 sx cement w/100 # hulls. Put 15 sx cement down rat hole.

GPS: 39.16616N -099.52053W

Perfs:

Top	Bot	Thru	Comments
3769	3774		

KCC WICHITA

Remarks: GLOBAL TICKET # 1320

MAY 21 2014

Plugged through: TBG

RECEIVED

District: 04

Signed Pat Bedore  
6/05/14 (TECHNICIAN)

CM

MAY 16 2014