

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-26259-00-00  
Spot: SESWNWSE Sec/Twnshp/Rge: 3-15S-20W  
1430 feet from S Section Line, 2170 feet from E Section Line  
Lease Name: NORTH TRUST Well #: 3-10-15-20  
County: ELLIS Total Vertical Depth: 3883 feet

Operator License No.: 34800  
Op Name: ROCK CREEK RESOURCES, LLC  
Address: 700 - 17TH STREET, SUITE 1300  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3814		130 SX
SURF	8.625	253		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/10/2014 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DEAN WALLACE Company: ROCK CREEK RESOURCES LLC Phone: (316) 841-4461

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement w/500 # hulls and 14 sx gel.  
DV Tool at 2025' w/420 sx  
Perforations at 3669' - 3674' Pawnee  
PBSD - 3793'

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/10/2014 11:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Consolidated rigged to casing and mixed and pumped 50 sx cement w/250 # hulls mixed in, followed by 14 sx gel, followed by 125 sx cement. Pressured well to 1200 psi. 1200 psi shut in pressure. Rigged to 8 5/8" casing and pumped 10 sx cement to pressure with 500 psi. 400 psi shut in pressure.

GPS: 38.77296 -099.53037  
SE SW NW SE  
1416' FSL 2151' FEL

Perfs:

Top	Bot	Thru	Comments
3669	3674		

KCC WICHITA

MAY 20 2014


RECEIVED

Remarks: CONSOLIDATED CEMENTING CO TICKET # 47580

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

CM

✓ 6/11/14

MAY 13 2014