

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-00115-00-00
Spot: SE Sec/Twnshp/Rge: 35-26S-40W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease Name: LAKE GAS UNIT Well #: 1
County: HAMILTON Total Vertical Depth: 2560 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		650		
PROD	4.5	2560	0	WITH 150 SX CMT
SURF	8.625	512		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/27/2014 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JASON SCHULER Company: ABERCROMBIE ENERGY Phone: (620) 793-8186

Proposed Plugging Method: PUMP 40 SX CMT & 200# HULLS AT 1950'. CIBP @ 650'. TEST CASING TO 700#. PERFORATE AT 640'. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/27/2014 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

LEFT IN HOLE 3 JOINTS OF WASH PIPE, 3 JOINTS OF 1 1/2" TBG & 6 JOINTS 2 3/8" TBG PUMP 40 SX CMT WITH 200# HULLS AT 1976' THROUGH TBG. CIBP @ 650'. TEST CASING TO 700#. HOLDING. PERFORATE 4 HOLES AT 640'. CIRCULATE CMT TO SURFACE THROUGH THE PERFORATIONS LEAVING THE 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS FULL OF CMT USING 175 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2528			
2506	2513		
2424	2435		
2372			
2356			

Received
KANSAS CORPORATION COMMISSION

JUN 06 2014

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 01

Signed [Signature]
(TECHNICIAN)
6/10/14

RECEIVED
MAY 30 2014
KCC DODGE CITY

Form CP-2/3
[Signature]