

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-21380-00-01  
Spot: S2S2N2SE Sec/Twnshp/Rge: 29-34S-20W  
1500 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: WAYNE Well #: 1-29  
County: COMANCHE Total Vertical Depth: 7160 feet

Operator License No.: 33513  
Op Name: FIVE STAR ENERGY, INC.  
Address: 215 E 14TH ST  
HARPER, KS 67058

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5475		
CIBP		6700		
CIBP		6810		WITH 2 SX CMT
CIBP		6940		
PROD	5.5	7390	3010	WITH 590 SX CMT
SURF	8.625	870		WITH 450 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/24/2014 10:00 AM  
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.  
Proposal Rcvd. from: JEFF BURK Company: FIVE STAR ENERGY Phone: (316) 250-5655

Proposed Plugging Method: CIBP @ 6795' WITH 2 SX CMT. PLUG AT 900' WITH 10 SX GEL & 50 SX CMT. PLUG AT 250' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/24/2014 4:50 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CIBP @ 6940'. SET CIBP @ 6810' WITH 2 SX CMT. 1ST PLUG AT 899' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 268' WITH 50 SX CMT. 3RD PLUG AT 43' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
6864	6866		
6845	6860		
6700			
5496	5500		
5475			
5433	5437		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

KCC WICHITA

MAY 12 2014

RECEIVED


District: 01

RECEIVED

MAY - 1 2014

KCC DODGE CITY

Signed

  
6/04/14 (TECHNICIAN)