

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20101-00-00
Spot: NWSE Sec/Twnshp/Rge: 23-23S-40W
1891 feet from S Section Line, 1841 feet from E Section Line
Lease Name: FRAZEE Well #: 1-23
County: HAMILTON Total Vertical Depth: 2520 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2519		350 SX
SURF	8.625	350		275 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/29/2014 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 100 SX CMT & 250# HULLS. DISPLACE WITH WATER TO 1000'. RUN CBL. LOG & PERFORATE AS REQUIRED. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/29/2014 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 100 SX CMT WITH 150# HULLS DOWN THE 4 1/2" CASING. DISPLACE TO 1100' WITH 17 BBLS WATER. RUN CBL FROM 1000' TO 15'. FOUND TOC @ 345'. RUN TBG TO 919' & SPOT 40 SX CMT BACK TO 250'. TOOH WITH TBG. PERFORATE 4 HOLES @ 245'. CIRCULATE CMT TO SURFACE USING 75 SX CMT LEAVING 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:


Top	Bot	Thru	Comments
2464	2468		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed


(TECHNICIAN)

RECEIVED
MAY - 5 2014

KCC DODGE CITY

KCC WICHITA

MAY 12 2014

RECEIVED

Form CP-2/3

