

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00154-00-00
Spot: NWNWSENE Sec/Twnshp/Rge: 7-21S-32W
3917 feet from S Section Line, 1258 feet from E Section Line
Lease Name: KOCH Well #: 1-7
County: FINNEY Total Vertical Depth: 2695 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2694	0	WITH 300 SX CMT
SURF	8.625	343		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/24/2014 1:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (405) 935-7290

Proposed Plugging Method: PMP 165 SX CMT WITH 250# HULLS. TEST CASING TO 200#. RUN CBL FROM 1100' UP TO DETERMINE TOC. PERFORATE & RUN TBG AS REQUIRED. MAY HAVE TO PERFORATE AT 1000' & AT 360' DEPENDING ON TOC.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/24/2014 6:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 150 SX CMT & 250# HULLS DOWN 5 1/2" CASING. DISPLACE TO 1600' & PRESSURE TO 600#. HOLDING. RUN CBL. BOND LOG TOOL NOT WORKING. PERFORATE 4 HOLES @ 936'. ESTABLISH INJECTION RATE 3 BPM @ 500#. PUMP 45 SX CMT, 50# HULLS THEN 45 SX CMT. DISPLACE TO 600' & PRESSURE TO 800#. PERFORATE 4 HOLES @ 365'. CIRCULATE CMT TO SURFACE USING 100 SX CMT, LEAVING 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2659	2669		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

RECEIVED
MAY - 5 2014
KCC DODGE CITY

Signed

Ken Jehlik
6/02/14
(TECHNICIAN)

KCC WICHITA

Form CP-2/3

MAY 12 2014

RECEIVED

MM