

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20124-00-00
Spot: W2W2E2E2 Sec/Twnshp/Rge: 22-21S-32W
2679 feet from S Section Line, 1294 feet from E Section Line
Lease Name: LEMON Well #: 1-22
County: FINNEY Total Vertical Depth: 2732 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2731	0	WITH 362 SX CMT
SURF	8.625	356		WITH 175 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/14/2014 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 90 SX CMT WITH 250# HULLS. DISPLACE TO 1300'. TEST CASING TO 700#. RUN CBL TO DETERMINE TOC. PERFORATE AND/OR RUN TBG AS REQUIRED.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/14/2014 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 90 SX CMT WITH 250# HULLS DOWN 4 1/2" CASING. DISPLACE WITH WATER TO 1300' & PRESSURE TO 700#. HOLDING. RUN CBL FROM 1300' TO 800'. NO CMT ABOVE 1200'. PERFORATE 4 HOLES AT 1180'. PUMP 45 SX CMT, 50# HULLS THEN 45 SX CMT. DISPLACE WITH WATER TO 900' @ 650#. PERFORATE 4 HOLES AT 380'. CIRCULATE CMT TO SURFACE WITH 55 SX CMT, LEAVING THE 4 1/2" CASING & 4 1/2" X 7" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2685	2724		

KCC WICHITA
MAY 27 2014
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed Ken Jehlik (TECHNICIAN)
6/03/14

RECEIVED
MAY 21 2014
KCC DODGE CITY