

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-20667-00-00  
Spot: SWNW Sec/Twnshp/Rge: 29-31S-40W  
1998 feet from N Section Line, 670 feet from W Section Line  
Lease Name: SHARP (ISRAEL #1) Well #: 2-29  
County: MORTON Total Vertical Depth: 5750 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: 6200 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1565		
CIBP		2131		WITH 2 SX CMT
CIBP		4972		WITH 2 SX CMT
PROD	5.5	5750	0	WITH 180 SX CMT
SURF	9.625	1510		WITH 700 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/08/2014 8:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: STEVE EMICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: SET CIBP @ 4972' WITH 2 SX CMT. SET CIBP @ 2131' WITH 2 SX CMT. RUN CBL TO DETERMINE ORDERS

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/08/2014 4:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 4972' WITH 2 SX CMT. SET CIBP @ 2131' WITH 2 SX CMT. COULDN'T GET HOLE TO LOAD. SET CIBP @ 1565' & RUN CBL TO FIND TOC @ 1524'. PERFORATE AT 1500' & PUMP 75 SX CMT. PERFORATE AT 550' & PUMP 125 SX CMT CIRCULATED TO SURFACE.

Perfs:

KCC WICHITA  
MAY 20 2014  
RECEIVED

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

MAY 14 2014

KCC DODGE CITY

Signed

*[Handwritten Signature]*  
6/03/14

(TECHNICIAN)