

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22334-00-01
Spot: NWNWNESE Sec/Twnshp/Rge: 7-10S-17W
2333 feet from S Section Line, 1118 feet from E Section Line
Lease Name: KLEINSCHMIDT B Well #: 9
County: ROOKS Total Vertical Depth: 3498 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3549		200 SX
SURF	8.625	218		150 SX

Well Type: EOR UIC Docket No: E12384.5 Date/Time to Plug: 05/06/2014 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1928

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations: 3304' - 3482'
DV Tool at 1396' w/350 sx cement

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/06/2014 1:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2900' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 1934' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 967' and pumped 50 sx cement. Circulated cement to surface. Topped off 4 1/2" casing w/40 sx cement. Hooked to 8 5/8" x 4 1/2" annulus and pumped 10 sx cement. Shut in pressure 200 psi.

GPS: 39.19705N -099.25503W

Perfs:

Top	Bot	Thru	Comments
3278	3496		

KCC WICHITA

MAY 21 2014

RECEIVED

Remarks: ALLIED TICKET # 55254

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

MAY 16 2014

Form CP-2/3