

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20038-00-01
Spot: NWSEENW Sec/Twnshp/Rge: 8-10S-17W
4309 feet from S Section Line, 3120 feet from E Section Line
Lease Name: WINTERS C Well #: 4
County: ROOKS Total Vertical Depth: 3535 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3558		275 SX
SURF	8.625	153		135 SX
T1	3.5	3459		175 sx

Well Type: EOR UIC Docket No: E13187.2 Date/Time to Plug: 05/09/2014 8:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL CO Phone: (785) 259-1928

Proposed Plugging Method: Ordered 225 sx 60/40 pozmix 4% gel cement
Squeezed hole at 3149' - 3181' w/50 sx cement
Perforations at 3420' - 3512'
DV Tool at 1400' with cement to surface

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/09/2014 9:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 3 1/2" casing and pumped 175 sx cement w/200 # hulls. Hooked to 8 5/8" annulus and pumped 5 sx cement. Shut in pressure 200 psi.

GPS: 39.20240N -099.24345W

Perfs:

Top	Bot	Thru	Comments
3502	3512		
3490	3494		
3483	3486		
3461	3469		
3443	3451		
3420	3430		

KCC WICHITA

Remarks: SWIFT TICKET # 26608 PLUGGED THROUGH 3 1/2" LINER

MAY 21 2014

Plugged through: CSG

RECEIVED

District: 04

Signed Pat Bedore
(TECHNICIAN)

CM

MAY 16 2014

Form CP-2/3