

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20068-00-00
Spot: SW Sec/Twnshp/Rge: 15-30S-31W
1316 feet from S Section Line, 1358 feet from W Section Line
Lease Name: BAUGHAM TRUST Well #: 1-15
County: HASKELL Total Vertical Depth: 2720 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		600		
CIBP		1750		WITH 2 SX CMT
CIBP		2640		WITH 2 SX CMT
PROD 4.5		2707	0	WITH 550 SX CMT
SURF 8.625		500		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/29/2014 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: STEVE EMICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: SET CIBP @ 2670' WITH 2 SX CMT. RUN CBL & FIND TOC & DETERMINE HOW TO PLUG.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/29/2014 2:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 2640' WITH 2 SX CMT. COULDN'T GET CASING TO LOAD. SET CIBP @ 1750' WITH 2 SX CMT. RUN CBL & FOUND TOC @ 640'. COULDN'T GET CASING TO LOAD. SET CIBP @ 600'. LOADED & PRESSURE TESTED CASING. PERFORATE @ 540' & PUMPED 250 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2690	2700		

KCC WICHITA
MAY 20 2014
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED

MAY 15 2014

KCC DODGE CITY

Signed

(TECHNICIAN)

Form CP-2/3