

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-22686-00-00  
Spot: NENESE Sec/Twnshp/Rge: 1-18S-11W  
2310 feet from S Section Line, 330 feet from E Section Line  
Lease Name: SMITH Well #: A-1  
County: BARTON Total Vertical Depth: 3249 feet

Operator License No.: 9952  
Op Name: BRACKEEN LINE CLEANING, INC.  
Address: 101 S 6TH ST PO BOX 434  
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3246		125 SX
SURF	8.625	305		300 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/05/2014 8:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: DARRIN SMITH Company: BRACKEEN LINE Phone: (620) 587-3351

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/12 sx gel and 400 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/05/2014 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 1400', 575' and 305'. Ran tubing to 3200' and pumped 12 sx gel followed by 60 sx cement w/100 # hulls. Pulled tubing to 1400' and pumped 80 sx cement w/100 # hulls. Pulled tubing to 600' and pumped 30 sx cement w/100 # hulls. Pulled tubing to 300'. Circulated cement to surface on casing with 40 sx cement. Pulled tubing. Tied to casing and circulated cement to surface on surface pipe with 60 sx cement.

GPS: 38.51387 -098.48188

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie  
6/05/14 (TECHNICIAN) *CR*

MAY 06 2014

KCC WICHITA Form CP-2/3

MAY 15 2014

RECEIVED