

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-21576-00-00  
Spot: NESWSW Sec/Twnshp/Rge: 28-11S-22W  
990 feet from S Section Line, 990 feet from W Section Line  
Lease Name: SHAW CREEK UNIT Well #: BR 14  
County: TREGO Total Vertical Depth: 4020 feet

Operator License No.: 9090  
Op Name: CHARTER ENERGY, INC.  
Address: PO BOX 252  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4020		1000 SX
SURF	8.625	286		190 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/19/2014 2:00 PM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: STEVE BAIZE / CHRIS SCH Company: PROFESSIONAL PULLING SERVIC Phone: (620) 793-9090

Proposed Plugging Method: Perforations at 3592' - 3793' and 3923' - 3933'  
157' tubing stuck in bottom of hole.  
2000' rods stuck in hole  
Casing leak at 1054'  
  
Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/19/2014 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 1900' and pumped 315 sx cement w/550 # hulls. Pulled tubing. Topped off casing w/20 sx cement. Tied on to back side and squeezed with 20 sx cement. Shut in pressure 200 psi.

GPS: 39.06210 -099.77512

Perfs:

Top	Bot	Thru	Comments
3923	3933		
3592	3793		

KCC WICHITA

Remarks: QUALITY CEMENTING TICKET # 188

MAY 28 2014

Plugged through: TBG

RECEIVED

District: 04

Signed [Signature]  
6/03/14 (TECHNICIAN)

CM

MAY 20 2014

Form CP-2/3