

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-075-20539-00-01  
Spot: W2NWNese Sec/Twnshp/Rge: 14-22S-42W  
2266 feet from S Section Line, 1297 feet from E Section Line  
Lease Name: CHEATUM Well #: 2-14  
County: HAMILTON Total Vertical Depth: 5375 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: 6200 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2657	0	WITH 510 SX CMT
SURF	8.625	1361		WITH 540 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/30/2014 2:00 PM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 85 SX MT WITH 250# HULLS. DISPLACE TO 1300'. BOND LOG & PERFORATE AT NECESSARY. RUN TBG IF NECESSARY. CIRCULATE CMT TO SURFACE FROM 1300' INSIDE & OUT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/30/2014 6:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 95 SX CMT & 250# HULLS DOWN 4 1/2" CASING. DISPLACE WITH WATER TO 1350'. RUN CBL FROM 1340' TO 70'. TOC @ 590'. PERFORATE 4 HOLES @ 550'. COULD NOT ESTABLISH CIRCULATION AT 1000 PSI. RUN TBG TO 1250'. CIRCULATE CMT TO SURFACE IN 4 1/2" CASING USING 85 SX CMT. TOP OFF WITH 5 SX CMT. PUMP 10 SX CMT DOWN THE ANNULUS TO 400#.

Perfs:

Top	Bot	Thru	Comments
2590	2604		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed

*Ken Jehlik*  
6/03/14

(TECHNICIAN)

KCC WICHITA

MAY 12 2014

RECEIVED

RECEIVED

MAY - 5 2014

KCC DODGE CITY

Form CP-2/3

*Bob*