

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19483-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 18-32S-5E
110 feet from S Section Line, 4995 feet from E Section Line
Lease Name: BARNETT Well #: 1
County: COWLEY Total Vertical Depth: 1890 feet

Operator License No.: 33277
Op Name: COOPER, ALBERT L. DBA COOPER SER
Address: PO BOX 381
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1890		50 SX
SURF	8.625	200		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/31/2014 8:00 AM
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L. DBA COOPER SERVICE CO.
Proposal Rcvd. from: ALBERT COOPER Company: COOPER SERVICE CO. Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 04/27/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/ BIT & TUBING CIRCULATING VARIOUS BRIDGES @ 1733'. 4-27-2014, W/ TBG @ 1733', COOPER SERVICE PUMPED 35 SXS 60/40 POZMIX 4% GEL & DISPLACED IN CASING. LAYED DOWN TUBING @ 305', COOPER SERVICE ESTABLISHED CIRCULATION & PUMPED 30 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. LAYED DOWN TUBING. PLUG DOWN 6:30 PM 4-27-2014. DANIELS READY MIX CEMENT TICKET # 30364. 4-28-2014, TAGGED CEMENT PLUG @ 15'. TOPPED WELL BACK TO SURFACE W/5 SXS.

Perfs:

Top	Bot	Thru	Comments
1885	1888	CSG	
1750	1755	CSG	

Remarks: COMPLIANCE / 10 YR RULE/ DENIED TA

Plugged through: TBG

KCC WICHITA
MAY 15 2014
RECEIVED

District: 02

Signed DUANE KRUEGER
6/04/14 (TECHNICIAN)