

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-21593-00-02  
Spot: NESWSWNE Sec/Twnshp/Rge: 5-33S-20W  
2280 feet from N Section Line, 2269 feet from E Section Line  
Lease Name: BYRAM Well #: 1-5  
County: COMANCHE Total Vertical Depth: 6700 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 522 N. MAIN ST PO BOX 560  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4880		
PROD	5.5	5464	3460	WITH 150 SX CMT
SURF	8.625	721		WITH 350 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/30/2014 12:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MATTHEW OSBORN Company: DAYSTAR PETROLEUM Phone: (620) 583-5527

Proposed Plugging Method: CIBP @ 4880'. SAND TO 4550' & 5 SX CMT. PLUG AT 960' WITH 15 SX GEL & 40 SX CMT. PLUG AT 750' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/30/2014 2:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CIBP @ 4880'. SANDED TO 4550' WITH 5 SX CMT. 1ST PLUG AT 958' WITH 15 SX GEL & 40 SX CMT. 2ND PLUG AT 753' WITH 50 SX CMT. 3RD PLUG AT 320' WITH 40 SX CMT. 4TH PLUG AT 42' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5013	5015		
4996	5000		
4984	4994		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

District: 01

Signed

*Eric MacLaren*

(TECHNICIAN)

RECEIVED

MAY - 1 2014

KCC DODGE CITY

KCC WICHITA Form CP-2/3

MAY 12 2014

RECEIVED