

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20162-00-01
Spot: NW Sec/Twnshp/Rge: 27-24S-31W
3942 feet from S Section Line, 3964 feet from E Section Line
Lease Name: COOVER-MOLER Well #: 1-A
County: FINNEY Total Vertical Depth: 2775 feet

Operator License No.: 34434
Op Name: EDISON OPERATING COMPANY LLC
Address: 8100 E. 22ND ST. N., BLDG 1900
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2749	733	WITH 150 SX CMT
SURF	8.625	614		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/05/2014 10:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SHOOT TBG OFF 2000-2300'. SPOT 20 SX CMT AT 2000'+/. CHECK STRETCH. PULL 1100' CASING. IF CAN'T PULL, MAY NEED TO SET PLUG WITH HULLS OVER CASING LEAK, THEN BLOW COLLAR AT 1100-1150'. PLUG AT 1150' +/- WITH 50 SX CMT. PLUG AT 650' +/- WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE
Date/Time Plugging Completed: 05/07/2014 4:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TBG STUCK IN SAND. CUT TBG AT 2000'. SPOT 25 SX CMT PLUG AT 1930'. PUMP 150# HULLS IN MUD TO 1500' TO SHUT OFF CASING LEAK. BLOW A CASING COLLAR AT 1162'. SPOT 50 SX CMT HALF IN AND HALF OUT OF CASING AT 500#. SHOOT CASING OFF AT 733' & PULL TO 650'. PLUG AT 650' WITH 50 SX CMT. CIRCULATED. PLUG AT 40' WITH 10 SX CMT. CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
2680	2700		


KCC WICHITA
MAY 20 2014
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed


(TECHNICIAN)
6/6/14

RECEIVED

MAY 13 2014

KCC DODGE CITY