

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-20784-00-00  
Spot: SWSENWNE Sec/Twnshp/Rge: 3-25S-31W  
4030 feet from S Section Line, 1890 feet from E Section Line  
Lease Name: VIOLET TATE Well #: 2-A  
County: FINNEY Total Vertical Depth: 2750 feet

Operator License No.: 34434  
Op Name: EDISON OPERATING COMPANY LLC  
Address: 8100 E. 22ND ST. N., BLDG 1900  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2748	530	WITH 525 SX CMT
SURF	8.625	503		WITH 280 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/29/2014 10:00 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SQUEEZE PERFS WITH 25 SX CMT & 200# HULLS. PLUG AT 1950' WITH 25 SX CMT. PLUG AT 1140' WITH 25 SX CMT. CUT CASING. PLUG AT 530' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE  
Date/Time Plugging Completed: 05/01/2014 11:00 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

PUMP 25 SX CMT & 200# HULLS AT 2600' THROUGH TBG. 1ST PLUG AT 1950' WITH 25 SX CMT. 2ND PLUG AT 1140' WITH 25 SX CMT. TAG TOC @ 810'. 3RD PLUG AT 530' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2650	2686		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed

*Kenny Sullivan*  
6/04/14

(TECHNICIAN)

KCC WICHITA

MAY 12 2014

RECEIVED

RECEIVED

MAY - 5 2014

KCC DODGE CITY

Form CP-2/3