

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-21093-00-00  
Spot: NENESE Sec/Twnshp/Rge: 33-29S-34W  
2319 feet from S Section Line, 327 feet from E Section Line  
Lease Name: ADAMS L Well #: 24W  
County: HASKELL Total Vertical Depth: 5700 feet

Operator License No.: 34545  
Op Name: ELM III OPERATING COMPANY LLC  
Address: 1249 E. 33RD  
EDMOND, OK 73013

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	5215		
DVT	5.5	3138		
PROD	5.5	5541	1878	WITH 130 SX CMT
SURF	8.625	1820		WITH 500 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/24/2014 11:30 AM  
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.  
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (405) 834-6997

Proposed Plugging Method: CIBP @ 5215'. PLUG AT 1850' WITH 20 SX GEL & 50 SX CMT. PLUG AT 700' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/24/2014 8:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

CIBP @ 5215' WITH 2 SX CMT. 1ST PLUG AT 1844' WITH 20 SX GEL & 50 SX CMT.  
2ND PLUG AT 684' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Top	Bot	Thru	Comments
5266	5296		

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR\*\* USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed

*[Handwritten Signature]*  
6/04/14  
(TECHNICIAN)

RECEIVED

MAY - 1 2014

KCC DODGE CITY

KCC WICHITA

MAY 12 2014

RECEIVED

Form CP-2/3

*[Handwritten Initials]*