



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

29 September 1981  
RECEIVED  
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

15-033-20,494-0000

OCT - 1 1981  
10-1-81  
CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Gary Bagby of Huskey Drilling Co. #2 Rig has this date requested permission to plug the following described well:

Operator's Full Name: Bow Valley Exploration

Complete Address: 1700 Broadway, Suite 900 Denver Colo. 80290

Lease Name: Selzer Well No. 2-17

Location: C-E 1/2 of NW 1/4 Sec. 17 Twp. 33S Rge. 19W (E) (4)

County: Comanche Total Depth: 5339'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  DSA

Other well as hereafter indicated: \_\_\_\_\_

Mr. Bagby was instructed to plug the well as follows:

There is 596' of 8 3/8" surface casing cement circulated. Circulate heavy mud at 1,000' for 10 min. 1st plug pumped to 1,000' with 1 skx hulls & 35 skx cement. 2nd plug pushed rubber plug to 570' with 1/2 skx hulls & 40 skx of cement on top of rubber plug. 3rd plug 40' to 0' with solid bridge & 10 skx of cement. Then put 5 lbs. in each rat hole & mouse hole. Plugging accomplished by Haliburton Co.

Very truly yours,

Paul Luttie  
Conservation Division Agent