



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

27 October 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-033-20491-0000

Dear Sir:

Mr. Bill Cheshire of Freeman Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Texas Oil & Gas Corp.

Complete Address: 200 West Douglas Suite 300, Wichita, Kans 67202

Lease Name: Jellison Well No. A-2

Location: 660' FSL-2310' FWL Sec. 5 Twp. 33S Rge. 19W (E) (W)

County: Comanche Total Depth: 5500'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Cheshire was instructed to plug the well as follows:

There is 670' of 8 3/8" surface casing cement circulated. The anhydrite is at 1400' top. All other fresh water is behind surface casing. After circulating heavy mud for 10 min. 1st plug 1600' with 35 sks of cement. 2nd plug pushed rubber plug to 650' then pumped 35 sks of cement on top of rubber plug. 3rd plug 40' to solid bridge with 10 sks cement. Then they put 5 sks in each the rat hole & mouse hole.

Very truly yours,

Paul Luthers
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
NOV 2 1981
11-2-81
CONSERVATION DIVISION
Wichita, Kansas

(over)

The water well is 64' deep with 5" casing. They were advised
about filling water well with coyp. con. ~~and~~ if the well is to
be left. If is to be plugged they are to pump 5 bbls of cement
into it. Plugging accomplished by Dowell cementing of
Pratt Kansas

Paul