

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed June 15, 1967.

Dear Sir:

Mr. Tom Curtis of Graham-Michaelis Drilling has this
date requested permission to plug the following described well:

Mr. Curtis guarantees payment of the plugging fee.

Operator's full Name: Graham-Michaelis Drilling, Inc.

Complete Address: 211 North Broadway, Wichita, Kansas

Lease Name: Einsel Well No. # 1-11

Location: App. C E/2 SW Sec. 11 Twp. 33 Rge. 17 (E)(W) W

County Comanche Total Depth 5200' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Curtis was instructed to plug the well as follows:

508' of 8 5/8" surface pipe, cement circulated with 400 sacks. Fill
hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of 2nd bridge and cement rat hole with 2 sacks.

JUL 17 1967

7-17-67
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

Archie Elving
Conservation Division Agent