

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

SEP 18 1963

J. P. Roberts.  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

CONSERVATION DIVISION  
 Wichita, Kansas

Dear Sir:

Mr. Vaughn Francis of Terrel Drilling & Producing this  
 date requested permission to plug the following described well:

Mr. Francis guarantees payment of the plugging fee.

Operator's full Name: Fred B. Anschutz

Complete Address: 1521 Wichita Plaza, Wichita, Kansas

Lease Name: Maude Carpenter (Trust) Well No. # 1

Location: NE SW Sec. 8 Twp. 33 Rge. 20 (E) (W) W

County Comanche Total Depth 5300 Oil Well       

Gas Well        Input Well        SWD Well        D & A X Lost Hole       

Mr. Francis was instructed to plug the well as follows:

80' of 13 3/8" conductor string, cemented with 250 sacks.

282' of 8 5/8" surface pipe, cemented with 275 sacks.

Fill hole with mud to 275', 1st cementing plug, 1/4 sack hulls,

cement with 20 sacks. Fill hole with mud to 40', 2nd cement-

ing plug, 1/4 sack hulls, cement with 10 sacks to base cellar.

Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent