

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-033-20,434-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Bow Valley Petroleum Inc.

Complete Address 1700 Broadway Suite 700 Denver Colo. 80290

Lease Name N. V. Lindsey Well No. 17-1

Location C-NE-NW Sec. 17 Twp. 33 Rge. 19 (East)(West)

County Comanche Total Depth 5350'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated Equipped & tested, never produced

Plugging Contractor Lillard Casing Pullers

Address Suite 417, 3022 North West Expressway Oklahoma City, Okla 73112 License No. 618

Operation Completed: Hour: 3:00 P.M. Day: 4 Month: May Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They ran & cemented 5327' of 4 1/2" production pipe. They plugged back to 5300' & perforated pipe at 4321' to 24'. 1st plug at bottom of hole with 2 bbls of bulls & 25 bbls of cement. 2nd plug at 593' with 50 bbls of cement. 3rd plug 40' to 0' with 10 bbls of cement. They recovered 2804' of 4 1/2" production pipe. They pumped the cement through production pipe with hole full of heavy mud. The plugging was accomplished by Lillard Casing Pullers.

Amount of Surface Casing: 431' of 8 5/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Raul A. Lutter
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

MAY 11 1982
5-11-82
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED

DATE 5-19-82

179-W
180