

KANSAS

FORM CP-3  
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-033-20,490-0000

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name Bow Valley Exploration

Complete Address 1700 Broadway, Suite 900, Denver Colo. 80290

Lease Name Watson Well No. 1-29

Location C-SW-SE Sec. 29 Twp. 33S Rge. 19W (East) (West)

County Comanche Total Depth 5385'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Huskey Drilling Co. Inc.

Address 200 E First, Suite 500, Wichita, Kansas 67202 License No. \_\_\_\_\_

Operation Completed: Hour: 6:30 P.M. Day: 14 Month: October Year: 19 81

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows:

There is 626' of 8 5/8" surface casing cement circulated. 1st plug circulated at 1000' for 10 min. then pumped down 40 bbl cement. 2nd plug 600' push rubber plug down and put 35 bbl cement on top of rubber plug. 3rd plug 40' to 0' on solid bridges with 10 bbl of cement. Then put 5 bbl cement in each mouse hole & rat hole. Plugging accomplished by Halliburton Co. out of Pratt Kans

RECEIVED

STATE CORPORATION COMMISSION  
10-19-81

I hereby certify that the above well was plugged as herein stated.

DATE 11-19-81

INV. NO. 8316-W

Signed: Paul Luth  
Conservation Division Agent