

KANSAS

FORM CP-3  
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-033-20,491-6000

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Texas Oil & Gas Corp.

Complete Address 200 West Douglas, Suite 300 Wichita, Kansas 67202

Lease Name Jellison Well-No. A-2

Location C E 1/2 E 1/2 SE SW Sec. 5 Twp. 33S Rge. 19W (East)(West)

County Comanche Total Depth 5500'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Treman Drilling Co.

Address 251 N. Water Wichita Kansas 67202 License No. \_\_\_\_\_

Operation Completed: Hour: 5:30 AM Day: 28 Month: October 1981

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

There is 672' of 8 5/8" surface casing cement circulated. The anhydrite is at 1400' top. All other fresh water formations behind surface casing. 1st plug at 1200' after circulating heavy mud for 10 min with 35 sbs of cement on solid bridge. 2nd plug pushed rubber plug to 650' then pumped 35 sbs cement on top of rubber plug. 3rd plug 40' to 0' on solid bridge with 10 sbs of cement. Then 5 sbs cement in each, the rat hole & the mouse hole. The water well is 64' with 5" casing. They have been advised about filing with Corp. Com. if farmer wants well. If not they are to put 5 sbs

I hereby certify that the above plugging instructions were given as herein stated.

DATE 11-24-81  
INV. NO. 8993W

Signed: Paul Luther  
Conservation Division Agent

(over)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV - 2 1981  
11-2-81  
CONSERVATION DIVISION  
Wichita, Kansas

of cement to bottom of it and record plugging. The  
Plugging accomplished by Dowell Cementing Co.  
Pratt Kansas.

Paul