

KANSAS

STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Intent to Drill,  
filed June 15, 1967.

Operator's Full Name Graham-Michaelis Drilling, Inc.  
Complete Address 211 North Broadway, Wichita, Kansas  
Lease Name Einsel Well No. # 1-11  
Location App. C E/2 SW Sec. 11 Twp. 33 Rge. 17 (E) (W) W  
County Comanche Total Depth 5200'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Graham-Michaelis Drilling, Inc.  
Address 211 N. Broadway, Wichita, Kansas License No.         
Operation Completed: Hour 4:30 A.M. Day 15th Month July Year 1967

The above well was plugged as follows:

508' of 8 5/8" surface pipe, cement circulated with 400 sacks. Hole  
was filled with drilling mud to 300', 1st cementing plug, bridged with  
2 sacks of dry cement and 1/2 sack of hulls on fluid at 300', and cemented  
with 33 sacks from 285' to 185'. Hole was filled with drilling mud to 40',  
2nd cementing plug, bridged with 1/2 sack of hulls on fluid at 40', and ceme-  
nted with 10 sacks to the base of the cellar. Rat hole bridged and cemented  
with 5 sacks.

This cementing was done by Sun Cementing Company

I hereby certify that ~~the above well was plugged~~ as herein stated.

INVOICED

JUL 17 1967

Signed: Archie Elving  
Well Plugging SupervisorDATE 7/17/677-17-67  
CONSERVATION DIVISION  
Wichita, KansasINV. NO. 5992-W